


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bk Bldg., Wichita, Kansas.

SINCLAIR PRAIRIE OIL CO.
Alvin Isorn No. 1.

SEC. 25 T. 19 R. 11W
SE NE SW
330' fr S & EL N $\frac{1}{2}$ SW $\frac{1}{4}$

Total Depth. 3307'
Comm. 6-20-36 Comp. 7-14-36
Shot or Treated.
Contractor.
Issued. 10-17-36

County. Barton



Elevation.

CASING:

13 " 196'
7 " 3297'
2 $\frac{1}{2}$ " tbg 3290'

Production. Pot. 441 Oil
No water .

Figures Indicate Bottom of Formations.

surface dirt & sand	202
red bed	570
shale	910
red bed	1050
salt & shale	1312
shale & lime shells	1482
shale & lime	1559
shale & shells	1759
lime	1868
shale & lime	1944
lime brkn	2000
lime	2076
shale & lime	2218
lime shells & shale	2398
lime	2468
shale & lime	2573
lime	2629
lime hrd	2686
lime	2735
limo brkn	2745
lime	2859
shale	2898
shale & shells	3046
lime K C	3272
shale & lime	3300
Top Siliceous	3297
lime oil pay	3307
Total Depth.	