

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
 Union National Bk Bldg., Wichita, Kansas.

SINCLAIR PRAIRIE OIL CO.
 Mina Isern No. 2.

SEC. 25 T.19 R.11W
 NE SE SW
 330' fr E & 990' fr
 SL

Total Depth. 3326'
 Comm. 5-7-36 Comp. 5-27-36
 Shot or Treated. 1000 & 3000 Gal. Acid.
 Contractor.
 Issued. 7-11-36

County. Barton.

Casing:
 12½" 165'
 7 " 3293'



Elevation.

Figures Indicate Bottom of Formations.

Production. 251 B.
 Potential.

surface	15
sand	45
shale & shells	950
salt	1155
shale & shells	1515
broken lime & shale	1600
shale & shells	1675
broken lime & shale	1895
shale	1920
shale & shells	2330
shale	2360
broken lime	2405
broken lime & shale	2485
shale & shells	2610
lime Topeka	2907
shale & shells	2995
broken lime	3020
lime K.C.	3100
broken lime & shale	3120
lime (Top Siliceous 3293)	3283
lime & shale	3292
Siliceous lime oil	3326
Total Depth	

Acidized with 1000 gal made 69 bbl oil.
 Acidized with 3000 gal made 251 bbl oil.