

WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - J. H. HERSHEY
Farm - Ernst

No. 1.

SEC. 26
C SE SE

T. 19

R. 11 W

Total Depth. 3305'

Comm. 5-31-43

Comp. 7-4-43


Shot or Treated.

Contractor. Veeder Sup&Dev.Co.

Issued. 2-19-44

County.

Barton
KANSAS



Elevation. _____

CASING:

8 5/8" 198'
5 1/2" 3302'

Production.

Min. Well

Figures Indicate Bottom of Formations.

surface clay	10
sand	110
shale	198
plug & cement 168-98	
shale & red bed	655
red bed	700
anhydrite, red bed	810
shale, lime, shells	985
salt shells & shale	1255
salt	1320
shale & shells	1370
lime & shale	1805
shale & shells	1905
lime & shale	2000
shale & shells	2046
drill pipe stuck, run	
Eason whipstock at 1443	
lime	1580-1620
lime & shale	1830
shale & shells	1925
lime & shale	1990
shale & shells	2125
lime, shale, shells	2230
shale & shells	2370
shale	2435
shale & shells	2555
lime & shale	2705
lime Topeka	2715
lime	2900
sdv lime & shale	2975
shale & lime	3040
lime	3075
lime & shale	3115
lime	3300
shale & lime	3301
Arbuckle lime	3305
Total Depth.	