

THE TEXAS CO.
H.C. Lanterman No. 1.


SEC. 27 T. 19 R. 11 W
CSW SW
660' S & W Lines-SW SW

DISCOVERY WELL

County. Barton

Total Depth. 3361'
Comm. 1-30-43 Comp. 3-1-43
Shot or Treated.
Contractor. Hisson Drlg. Co.
Issued. 6-19-43

Rotary O-3333
Cable 3333-61



CASING:
10 3/4" 250' Cem.
5 1/2" 3333' Cem.

Elevation.

Production. Pot. 26 B.
Pmpg, No wtr
Figures Indicate Bottom of Formations.

sand & clay blue	224
red bed & shale	250
shale & shells	1020
salt	1320
shale & shells	1480
lime	1550
sdv lime & shale	1725
lime brkn	1830
lime	2015
lime brkn	2185
shale & shells	2475
lime & shale	2675
lime	2940
lime & shale	2956
shale & shells	3062
lime	3126
lime brkn	3208
lime & shale	3266
lime	3345
lime hd	3347
lime sft	3348
lime, some shale	3350
lime hd	3358
lime brown sft	3361
Total Depth.	

Tops: Heebner	2829
Lansing	3056
Conglomerate	3329
Arbuckle	3331

Ran Schlumberger

Acidized w/4100 Gals. Acid
4- 1000 Gal. treatments
1- 100 Gal. treatment