


**WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY**  
**508 East Murdock, Wichita, Kansas**

Company- EL DORADO REFINING COMPANY  
 Farm- Schwamborn No. 1

SEC. 28 T. 19 R. 11W  
 NW NW SW

Total Depth. 3383  
 Comm. 3-7-53 Comp. 3-24-53  
 Shot or Treated.  
 Contractor. Pabco Drilling, Inc.  
 Issued. 5-23-53

County Barton  
 KANSAS



**CASING:**  
 8 5/8" 280' cem w/160 sx  
 5 1/2" 3300' cem w/ 75 sx

Elevation. 1786

Production. 185 BOPD & no wtr

Figures indicate Bottom of Formations.

sand	95
shale, shells	287
shale, shells, redbeds	1000
salt, shale	1375
lime, shale	2665
lime	2884
lime, iron	2916
lime	2935
shale, lime	3050
lime	3279
lime, shale	3373
lime	3383
Total Depth	

Tops: D.F.	
Heebner	2925
Dodge	2944
Douglas	2958
Brown Lime	3047
Lansing	3066
Conglomerate	3335
Arbuckle	3372

DST 3084-94 open 30 mins.  
 weak blow 8 mins. rec. 30'  
 mud no show BHP 550#.

DST 3202-12 gas to surf,  
 48" open 1 hr. rec. 60' O & GCM &  
 110' muddy press. bomb stock.  
 No BHP.

ST & SLM OK @ 1000  
 ST & SLM OK @ 1500, 2000, 2700