


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- ELDORADO REFINING CO.
Farm- Schwamborn No. 3

SEC. 28 T. 19 R. 11W
NE NE SW

Total Depth. 3366
Comm. 9-16-53 Comp. 9-24 -53
Shot or Treated.
Contractor. Pickrell Drlg. Co.
Issued. 11-21-53

County Barton
KANSAS



Elevation. 1781

Production. 159 BOPD & 10% wtr

CASING:

8 5/8" 259' cem. w/175 sx
5 1/2" 3223' cem. w/ 75 sx

Figures indicate Bottom of Formations.

Meas. from top of R.B.

sand	105
sand & pyrite	170
shale	240
redbed	560
Anhydrite	585
shale	1140
salt	1230
shale & lime shells	1430
lime	1980
shale	2240
shale & shells	2645
lime	2765
shale & lime	2775
lime	2835
lime & shale brks	2910
lime	3366

Rotary Total depth

Tops: D.F.

Heebner	2921
Toronto	2938
Brown lime	3041
Lansing	3062
Conglomerate	3341

DST 3067-91 op. 1 hr. gd. blo.
rec. 60' sli. O & GCM & 600' gas.
GHP 220#/15"
DST 3123-41 op. 1 hr. gas to surf./13"
rec. 1340' oil, 30' mud & 500' wtr.
BHP 780#
DST 3199-3217, op. 1 hr. rec. 240'
gas & 10" GCM. BHP 80#
DST 3265-81 op. 1 hr. rec. 30' sli. OCM.
Very wk. blo. BHP 45#/15"
Perf. (18) 3128-31 ϕ 8 BO & 3 1/2 BW / 3 1/2 hrs.
1300' FIH o'nite ϕ 40 BF (23.75 BW & 16
BO/14 hrs.