


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- PABCO DRILLING, INC. et al
 Farm- Thill No. 1

SEC. 28 T. 19 R. 11W
 SW SW NW

Total Depth. 3366'
 Comm. 1-17-53 Comp. 1-25-53
 Shot or Treated.
 Contractor. Pabco Drlg. Inc.
 Issued. 4-25-53

County Barton
 KANSAS



Elevation. 1786 DF

Production. 312 Bbls. no wtr.

CASING:

8 5/8" 223' cem w/125 sx.
 5 1/2" 3366' cem w/ 50 sx.

Figures Indicate Bottom of Formations.

surface clay, sand	40
sand	110
shale, sand	145
shale, shells	223
shale-	320
red beds	575
anhyd,	595
shale, shells, red bed	1090
shale, salt	1250
shale, lime	1715
shale, shells	1790
shale, lime	2770
lime	2912
lime, shale	3049
lime	3122
lime, shale	3175
lime	3220
lime, shale	3345
lime	3366
Total Depth	
Tops :RB meas.	
Heebner	2940
Brown Lime	3059
Lansing	3078
Porous zone	3214 -3219
sandy congl.	3335
chat congl.	3350