

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

STANOLIND OIL & GAS CO.
H.C. Burmeister No. 2

SEC. 33 T. 19 R. 11W.
NE NE SW
2310' N of S.L.
2310' E of WL.
County Barton.

Total Depth. 3364
Comm. 1-19-37 Comp. 3-9-37
Shot or Treated. 1000 & 2000 Gals.
Contractor.
Issued. 4-17-37 Rotary O-3325
Cable 3325-64



CASING.

13" 199'5"
7" 3325'3"

Elevation.

Production. DRY.

Figures Indicate Bottom of Formations.

surface sand	19
sand and shells	112
shale and shells	260
red rock	265
shale and shells	515
anhydrite	540
shale and shells	1350
lime	1400
shale and shells	1437
broken lime	2037
shale and shells	2600
broken lime	2656
lime	2835
broken lime	2943
shale and shells	3022
broken lime	3145
lime	3299
shale green & gray	3315
shale red	3324
dolomite Top Siliceous	3327
lime slight porosity	3332
lime with shale strks	3334
lime hard gray	3339
$\frac{1}{2}$ B. Oil no water per hour	3337
lime soft brown No inc.	3341
lime hard white	3355
Acidized with 1000 gal.	
3342 no increase then acidized	
with 2000 gal and made 3 bbls per hr	
$\frac{1}{3}$ wtr.	
shale	3358
lime hard	3364
hole filled 100' per hr with	
water.	
Total Depth.	

Lansing 3075-3299
Siliceous lime 3324-3364