


STANOLIND OIL & GAS CO.
Rose Schartz No. 1.

SEC. 34 T. 19 R. 11W
SEc SE
330'N SL 2310' E WL

County. Barton



Elevation.

Production. Pot. 451 B.

Figures Indicate Bottom of Formations.

clay & sand	60
clay & shale shells	202
shale & shells	520
anhydrite	545
shale & shells	1012
salt	1265
shale & shells	1374
lime & shale	1517
shale & shells	1651
shale	1695
lime	1744
lime & shale	1823
brkn lime & shale	1957
lime	2018
shale	2062
shale & shells	2310
shale	2320
lime	2387
lime & shale	2573
lime brkn	2625
lime	2901
brkn lime & shale	2982
brkn lime	3018
shale	3049

Top Lansing 3045

lime	3055
Core #1 19/19 Recovery	
lime tan and grey dense	3068
shale grey	3071
lime grey	3074
lime	3100
lime & shale	3186
lime	3275

Core #2 18/20 Recovery

lime grey	3282
shale green	3289
conglomerate, lime, cherty, pyritic & shale	3295

Core #3 2/10 Recovery

conglomerate, cherty, shale, grey	3300
--------------------------------------	------

dolomite tan very

cherty	3302
--------	------

dolomite brown med xyl,

porous-fair to good

sat.	3305
------	------

Cable Tools

No record 3305-3306

Core #1 0/2 Recovery

No record 3306-3308

Core #2 2/2 Recovery

lime hrd, no inc in oil 3310

Total Depth.

Shooting

10 Qts. SNG 3305 $\frac{1}{2}$ -3310

Siliceous lime 3300-3310

Production 23 B.P.H. - Two hr
swabbing test.

Production 2nd 24 hrs. 451 B.
state potential.