


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

STANOLIND OIL & GAS CO.
C. Schmidt No. 2

SEC. 35 T. 19 R. 11W.
NE NE SE
2310' N of S.L.
2310' E of W.L.

Total Depth. 3316'
Corm. 10-20-37 Comp. 11-7-37
Shot or Treated. 30 qts 3307-3316 @500,2000&3000 gal County Barton.
Contractor.
Issued. 1-1-38 Rotary 3299
Cable 3316



Elevation.

Production. Pot. 406 B.

CASING.

103/4" 212'
6" 3293'

Figures Indicate Bottom of Formations.

shale and sand	212
red shale and sholls	475
anhydrite	520
shale red	538
shale and sholls	1000
salt and shalo	1323
lime and shalo	1448
broken lime	1670
lime	1735
lime and shale	1905
lime	2030
shale	2218
shale and lime	2553
lime	2956
lime and shale	3032
lime	3200

coring record. - Rotary.

1 3230-3237 7"/7 Rec.

sdv lime with shale

partings 3237

2 3237-3299 5"/12 Rec.

conglomerate shaloy 3293

Dol. grey no sat. 3294

dol. brown porous little

sat. 3296

dol. good sat. 3299

By samples Top siliceous 3293

Coring Record. Cable tools.

hard lime 3313

lime small show of oil 3316

Total Depth.

siliceous lime 3293-3316

swabbed 9 bbls per hr after swabbing and shotting thto 6" OD casing.