


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY:
Union National Bk Bldg, Wichita, Kansas.

CONTINENTAL OIL COMPANY:
A. Risse No. 5.

SEC: 36 T. 19 R. 11W.
SE SW SE
330'N 990' E of S/4 cor.

Total Depth. 3297
Comm. 2-27-36 Comp. 3-31-36.
Shot or Treated. 4000 gal
Contractor.
Issued. 6-13-36.

County. Barton.



CASING:

13" 172' 7" 3279'

Elevation.

Production. Pot. 1816 B.

Figures Indicate Bottom of Formations.

sand and shale	126	lime	3255
lime and shells	170	broken lime	3279
shale	176	lime	3297
shale and shells	480	Total Depth.	
shale and lime	585		
shale and shells	967		
shale	995	Top of Kansas City	3000'
salt	1144	Top of Siliceous	3278
salt and lime	1217		
shale	1260	Show oil	3282-3284
shale	1275	Increase oil	3284-3286
broken lime	1340	Total fill up 500' oil	3288
broken lime and shale	1385	Swab 15 bbls per hr	3291
shale and lime	1434	Increase oil	3291-3294
lime	1460	Swab 170 bbls	4 hours.
shale	1489		
lime	1515		
lime and shale	1555	4-2-36 Swab	66 bbls 11 1/4 hours.
shale and shells	1673	4-3-36	4000 gal acid.
lime and shells	1730	4-7-36 Pump	1521 bbls 19 hours
shale and shells	1785	4-8-36 Pump	1816 bbls 24 hours Pot.
shale and lime	1850		
lime	1870		
shale	1895		
shale and lime	1975		
lime	2010		
shale and shells	2290		
lime	2310		
shale and shells	2500		
lime	2538		
lime and shale	2560		
shale	2600		
lime	2880		
shale and shells	2985		
lime	3087		
shale	3095		
lime	3103		
lime and shale	3113		
broken lime	3120		