


TEXAS COMPANY.
C. Schmidt No. 5

SEC. 36 T. 19 R. 11W.
SW NE NW
990' N & EL NW $\frac{1}{4}$

Total Depth. 3292.
Comm. 7-7-37 Comp. 7-30-37
Shot or Treated. 1000 gal.
Contractor. J. E. Trigg.
Issued. 9-4-37 Rotary 3285
Cable 3292

County Barton.



CASING.

13" 200' 7" 3285'

Elevation.

Production. Pot. 1953 B.

Figures Indicate Bottom of Formations.

surface	205
shale and shells	1046
salt	1232
shale and shells	1335
lime	1431
shale and shells	1595
sdv lime	1625
broken lime	1732
shale	1809
lime	1840
shale and shells	2046
lime hard	2063
sticky shale	2094
lime	2120
shale	2146
shale and shells	2235
shale	2250
sdv lime	2316
shale and shells	2375
shale	2395
lime	2417
shale and shells	2558
lime	2753
shale and shells	2835
lime	2896
shale and shells	2977
lime	3002
shale and shells	3063
lime	3090
shale and shells	3110
lime	3280
shale	3289
lime	3292
Total Depth.	