

25-19-12W


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company - W. L. HARTMAN
Farm - Petz No. 1

SEC. 25 T. 19 R. 12W
NW NW NW

Total Depth. 3443
Comm. 10-9-49 Comp. 10-22-49
Shot or Treated.
Contractor. H & H Drilling Co.
Issued. 12-31-49

County. Barton
KANSAS



CASING:
8 5/8" 172' cem w/165 sx.

Elevation. 1802 *feet*.

Production. Dry and Abandoned

Figures Indicate Bottom of Formations.

clay	35
sand	150
iron	165
shale blue	172
shale	340
red bed	523
shale	613
anhydrite	635
shale, shells	1070
salt, shale, shells	1379
shale, lime	1624
lime	1805
lime, shale	1899
lime	1967
lime, shale	2596
lime	2708
lime, shale	2782
lime	3363
lime, conglomerate	3382
conglomerate, cherty	3401
conglomerate	3428
arbuckle	3443
Total Depth	

Tops: (D.F. Corr. 2' for Rotary Bushing)

Topeka	2724
Heebner Shale	2963
Brown Lime	3082
Lansing Kansas City	3101
Marmaton	3348
Sooy Conglomerate	3353
Arbuckle	3411

Geological Report:

- DST #1, 3104-3112, Open 30 mins, weak blow 5 mins. Rec. 10' mud.
- DST # 2, 3188-3195, open 20 mins, few bubbles. Rec. 10' mud.
- DST #3, 3237-3246, open 60 mins, weak blow 5 mins. Rec. 15' mud BHP Off.