

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

23-19-12W


Company - ALADDIN PETROLEUM CORP.
Farm - Brodie No. 2

SEC. 23 T. 19 R. 12W
NE SW SE

Total Depth. 3370 G.M.
Comm. 2-13-49 Comp. 3-5-49 ✓
Shot or Treated. 2000 gals acid.
Contractor. Hannum Drlg. Co.
Issued. 4-16-49

County. Barton

KANSAS



Elevation. 1809 feet.

CASING:

8 5/8" 217' RM cem w/100 sx.
5 1/2" 3349' GM cem w/150 sx.

Production. 476 K.C.C. test
after 2000gal. acid.

Figures Indicate Bottom of Formations.

shale, sand	35
sand, gravel	90
shale, shells	167
pyrite, shale	180
shale, shells	223
sand, shells	405
redbed, shells	527
shells, shale, redbed	800
shale, shells	1085
salt, shells	1200
shale, shells	1625
sand	1635
shale, shells	1785
lime	1990
lime, shale	2415
lime	2485
lime, shale	2650
lime	2962
Heebner shale	3010
Douglas sand	3021
shale, lime	3093
lime	3317
lime, shale	3355
Arbuckle	3348 GM
lime	3370 GM

Total depth
Rotary total depth 3357
Tops:

Heebner	2959
Douglas	3010
Brown Lime	3077
Lansing/K.C.	3095
Arbuckle	3349