

23-19-12W

WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


Company - ALADDIN ANDHANNUM
Farm - Brodie No. 4

SEC. 23 T. 19 R. 12W
SW NW SE

Total Depth. 3374
Comm. 4-15-49 Comp. 4-25-49
Shot or Treated.
Contractor. Hannum Drilling Co.
Issued. 6-4-49

County. Barton

KANSAS



Elevation. 1811 *Ind*

Production. 206 Bbls.

CASING:
8 5/8" 232' cem w/115 sx.
5 1/2" OD 3357' cem w/150 sx.

Figures Indicate Bottom of Formations.

clay yellow	30
sand	100
shale, shells, sand	130
shale, shells	235
pyrite, shale	280
sand	310
pyrite, redbed, shale	535
shale, red bed	622
anhydrite	649
shale, shells	1030
salt, shells	1150
shale, shells	1500
lime, shale	1621
lime, sand	1630
lime, shale	1745
shale, shells	1840
lime	1920
lime, shale	2657
lime brkn	2706
lime	2960
Heebner shale	2996
sand	3005
lime, shale	3086
lime	3280
lime, shale	3356 $\frac{1}{2}$
lime RTD	3358
lime	3374
Total Depth	

Tops: D. F.

Kansas City	3101
Arbuckle	3352 $\frac{1}{2}$

Deduct 3' from above to equal
derrick floor measure.