

FEB 15 1968 COMPANY Clinton Oil Company

SEC. 23 T. 19S R. 12W  
LOC. C W/2 NE NE

FARM Stueckemann NO. 1-V

COUNTY Barton


TOTAL DEPTH 3,400'

COMM. November 30, 1968 COMP. December 9, 1968

SHOT OR TREATED

CONTRACTOR H-30, INC.

ISSUED



CASING

20	10		
15	8	-5/8" 250' cemented w/185 sx cement	ELEVATION 1816 KB
12	6		
13	5	-1/2" 3390' cemented w/100 sx cement	PRODUCTION <i>Simple</i>

FIGURES INDICATE BOTTOM OF FORMATIONS


ELECTRIC LOG TOPS

Surface Soil, Sand & Shale	120	Anhydrite	632	+	1184
Sand & Shale	250	Base Anhydrite	654	+	1162
Shale & Red Bed	580	Howard	2630	-	814
Shale	634	Topeka	2713	-	897
Anhydrite	655	Heebner	2977	-	1161
Shale	1150	Toronto	2996	-	1180
Shale, Salt & Lime Streaks	1500	Douglas	3013	-	1197
Lime & Shale	1720	Douglas Sand	3026	-	1210
Lime & Shale Streaks	1896	Brown Lime	3094	-	1278
Lime & Shale	2250	Lansing	3110	-	1294
Shale & Lime	2550	Arbuckle	3372	-	1556
Shale & Lime Streaks	2730	Log T.D.	3399	-	1583
Lime	3400	Rotary T. D.	3400	-	1584
Rotary Total Depth	3400				

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

*Arlo B. Romer*  
Arlo B. Romer



STATE OF KANSAS }  
COUNTY OF SEDGWICK } SS:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 18th day of December, 1968.