

WELL LOG BUREAU-- KANSAS GEOLOGICAL SOCIETY
Wichita, Kansas

23-19-12W


Company - Aladdin Pet. Corp.
Farm - Wagner No. 6

SEC. 23 T. 19 R. 12W
NE NE SW

Total Depth. 3383
Comm. 8-31-49 Comp. 9-14-49
Shot or Treated. 500 gals. acid
Contractor. Hannum Drlg. Co.
Issued. 11-12-49

County. Barton

KANSAS



Elevation. 1816 *ft*

Production. 223 B/D

CASING:

8" set @ 235' w/115 sx.
5" set @ 3366' w/150 sx.

Figures Indicate Bottom of Formations.

Clay, sand & shale	175
Pyrites	182
Shale & shells	310
Red Bed & shale	640
Anhydrite	655
Shale & shell	1030
Shale, shells & salt	1130
Shale, shells & red bed	1350
Lime & shale	1620
Sand	1630
Lime	1635
Shale & lime	2645
Lime	2672
Lime & shale	2742
Lime	2950
Lime & shale	3025
Shale & sand	3040
Lime & shale	3115
Lime	3353
Shale	3367
Lime	3383

Total Depth

Tops:
Lansing 3107 G.M.
Arbuckle 3363 G.M.
Total depth 3383 G. M.