

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock,
Wichita, Kansas

22-19-12W

Company- C. U. BAY
Farm- Christoph

No. 1

SEC. 22
SW SE SE

T. 19

R. 12W

Total Depth. 3445

Comm. 11-24-51

Comp. 12-6-51


County Barton

KANSAS

Shot or Treated.

Contractor. Pickrell Drlg.

Issued. 1-19-52



CASING:

8 5/8" 170' cem. w/150 sx. circ.

Elevation. 1818

Production. Dry

Figures Indicate Bottom of Formations.

Meas. from top rotary bushing.

sand & shale	165
pyrite	170
iron	190
shale	650
anhyd.	670
shale & salt	1210
shale & shells	1495
lime	1885
shale & lime	1955
lime	2115
shale	2315
shale & shells	2440
shale & lime	2555
shale	2655
lime	2730
lime & shale	2805
lime	3380
congl.	3404
lime	3442
congl.	3445 RTD
Total Depth	

Tops:

Lansing	3114
Congl.	3371
Arb.	3433

D.S.T. 3115-48 op 45" Rec. 45' mud
790#

D.S.T. 3148-87 g 1 hr. rec. 55' sli.
wtr cut mud

D.S.T. 3245-64 op 45" Rec. 10' mud
0 BHP

D.S.T. 3269-98 op 1 hr. rec. 90'
drlg. mud 60' wtr mud, tr. oil BHP 1050#