

14-19-12W

KANSAS WELL LOG BUREAU--- KANSAS GEOLOGICAL SOCIETY
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY MURFIN DRILLING CO. & ALEDO OIL & GAS CO

SEC. 14 T. 19 R. 12 W
LOC. SW SW NE

FARM Gill

NO. 2

TOTAL DEPTH 3446

COMM. 2-7-51


COMP. 3-3-51

SHOT OR TREATED

CONTRACTOR Murfin Drilling Co.

ISSUED 5-5-51

COUNTY Barton KANSAS



CASING

8-1/4 209
5-3/16 3415

ELEVATION 1849 D. F.
1848 Ind.

PRODUCTION Dry

FIGURES INDICATE BOTTOM OF FORMATIONS

shale	35
sand	115
shale-shells	380
red bed	669
Anhydrite	692
red bed & shells	1170
salt & shells	1430
shale & shells	1525
shale & lime	1746
sandy lime	1755
shale & lime	1830
lime	1925
shale & lime	2575
shale	2670
shale & lime	2815
lime	3000
lime & shale	3310
lime	3390
lime & shale	3425
lime	3446
Total Depth	
Tops-Derrick Floor	
Topeka	2759
Heebner	3013
Brown Lime	3130
Lansing	3147
Arbuckle	3412

Acidized @ 3431 w/500 gal.

Set plug @ 3240

40 shots 3178-40

23 shots 3226-20

14 shots 3206-02

16 shots 3199-95

Acidized with 2000 gal.

650 ft. of water & no oil