

10-19-12W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- NADEL & GUSSMAN  
Farm- Eppstein No. 2

SEC. 10 T. 19 R. 12W  
SE NE SW

Total Depth. 3420'  
Comm. 9-4-60 Comp. 9-13-60  
Shot or Treated.  
Contractor. Jones Drlg.  
Issued. 11-26-60

County Barton  
KANSAS



Elevation. 1831' DF

Production. 122 BOPD

CASING:

8 5/8" 220' cem w/150 sx.  
4 1/2" 3320'

Figures Indicate Bottom of Formations.

shale	190
iron	200
sand & Anhydrite	210
iron	221
shale & redbed	595
shale	654
Anhydrite	682
shale & shale	1385
shale	1450
lime	1625
lime & shale	3170
lime	3410
shale & lime	3420
Total Depth	

TOPS:

Anhydrite	654
Heebner Shale	2998
Brown Lime	3112
Lansing-Kansas City	3124
Kansas City	3356

DST #1 3115-3140', op 90 min., good blow,  
Rec. 1500' gas plus 34' gcm plus show oil.  
IBHP not taken, FBHP 305#/30 mins, (still  
building).

DST #2 3156-3190', op 1 hr-strong blow  
gas to surf. in 40 mins., rec. 180' gcm  
plus 180' ho & gcm plus 120' muddy oil.  
IBHP 1015#, FBHP 980#, IFP 120#, FFP 195#.

DST #3 3196-3210', op 1 hr, weak blow,  
rec. 20' slightly oil cut muddy water.  
IBHP 355#/15 mins., FBHP 435#/30 mins.,  
FP 0#.

DST #4 3280-3310', op 1 hr, good blow,  
rec. 780' slightly oil cut salt water.  
IBHP 795#/ FBHP 650#, IFP 90#, FFP 405#.