

10-19-12W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
500 East Murdock, Wichita, Kansas

Company- NADEL & GUSSMAN
Farm- Lucas No. 2

SEC. 10 T. 19 R. 12W
SW SE NW

Total Depth. 3436'
Comm. 8-27-60 Comp. 9-3-60
Shot or Treated.
Contractor. Jones Drlg.
Issued. 11-19-60

County Barton
KANSAS



Elevation. 1831' DF

Production. 204 BOPD

CASING:

8 5/8" 226' cem w/150 sx.
5 1/2" 3434'

Figures indicate Bottom of Formations.

shale	205
iron	226
shale	276
shale & redbed	656
Anhydrite	685
shale & shells	1485
lime & shale	3166
lime	3416
lime & shale	3436 RTD
Total Depth	

TOP: ELECTRIC

Anhydrite (driller)	656
Topeka "Zone"	2900
Heebner	3001
Brown Lime	3113
Lansing-Kansas City	3128
Base Kansas City	3360
Cherty Conglomerate	3396
Arbuckle	3427

DRILL STEM TESTS:

#1 3132-3166', op 1 hr; fair, steady blow thruout. Rec. 2600' gas, 120' oil & gas cut mud. ISIP 1023#/20", IFP 22#, FFP 44#, FSIP 158#/20" (building slowly).

#2 3164-3190', op 1 hr., gas to surface in 4 mins., (too small to measure). Rec. 2580' clean, gassy oil. ISIP 1023#/20", IFP 156#, FFP 424#, FSIP 912#/20".

#3 3197-3210', op 1/2 hr., weak blow for 2", died. Rec. 10' mud. ISIP 845#/20 mins. IFP 0#, FFP 0#, FSIP 401#/20 mins.