

10-19-120


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- NADEL & GUSSMAN
Farm- Bryant No. 1

SEC. 10 T. 19 R. 12W
SW SW NE

Total Depth. 3430'
Comm. 9-20-60 Comp. 9-27-60
Shot or Treated.
Contractor. Jones Drlg.
Issued. 11-26-60

County Barton
KANSAS



Elevation. 1829' DF

CASING:
8 5/8" 210' cem w/150 sx.

Production. Dry

Figures Indicate Bottom of Formations.

sandy shale & shells	208
iron	216
white sand - pyrite	260
shale & redbed	640
shale & shells	658
Anhydrite	685
shale & shells	1290
lime & shale	2005
shale & shells	2225
shale	2695
lime & shale	2890
lime	2955
lime & shale	3145
lime	3160
lime & shale	3200
lime	3320
lime & shale	3430 RTD
Total Depth	

TOPS:	
Anhydrite	658
Heebner Shale	2999
Brown Lime	3113
Lansing-Kansas City	3127
Base Kansas City	3360
Conglomerate	3392
Arbuckle Dolomite	3423

DST #1 3128-3160', op 30 mins., weak blow
5 mins., died(flushed tool). Rec. 10'
oil specked mud, IBHPO#/30 mins., IFP 0#,
FFP 0#, FBHP 0#/30 mins.

DST #2 3166-3200', op 30 mins., weak blow
for 2 mins., died, flushed tool. Rec. 3'
mud. IBHP 140#/20 mins., IFP 0#, FFP 0#,
FBHP 0#/20 mins.