

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


10-19-12W

Company- NADEL & GUSSMAN
Farm- Schartz No. 1

SEC. 10 T. 19 R. 12
SW NW SE

Total Depth. 3433'
Comm. 10-1-60 Comp. 10-8-60
Shot or Treated.
Contractor. Jones Drlg.
Issued. 1-7-61

County Barton
KANSAS



CASING:
8" 214'
5" 3431'

Elevation. 1834' DF

Production. 200 BOPD

Figures Indicate Bottom of Formations.

shale	214
shale & shells	657
Anhydrite	685
shale & shells	1290
lime & shale	1870
shale	2350
lime & shale	2540
shale & shells	2720
shale & lime	2855
lime	2908
lime & shale	3100
lime	3433
Total Depth	

TOPS:

Anhydrite	657
Heebner Shale	3000
Brown Lime	3113
Lansing-Kansas City	3126
Base Kansas City	3357
Conglomerate	3396

DST #1 3155-3192', op 1 hr 15 min, gas to surf. in 23 min, rec. 1380' gassy oil, IBHP 920#, FBHP 895#/30 min, IFP 105#, FFP 330#.

DST #2 3192-3210', op 1 hr, good blow, rec. 120' gcm plus 360' muddy salt water. IBHP 815#/20 min, FBHP 740#/30 min, IFP 195#, FFP 80#.