

11-19-12W

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
505 East Murdock, Wichita, Kansas


Company- INGER OIL CO.
Farm- Miller No. 1

SEC. 11 T. 19 R. 12W
NE NE NW

Total Depth. 3420'
Comm. 9-17-60 Comp. 9-29-60
Shot or Treated.
Contractor. Duke Drlg.
Issued. 11-26-60

County Barton

KANSAS



Elevation. 1806' KB

Production. Dry

Figures Indicate Bottom of Formations.

sub soil & clay	30
sand	65
shale	145
sand	163
shale	190
broken sand	204
shale	241
sand	245
shale	262
sand	269
shale	350
red bed	632
Anhydrite	670
shale shells	1150
salt & shale	1400
shale & lime	1975
lime & shale	2680
lime	2982
shale Heebner	2986
lime & shale	2995
lime Toronto	3003
shale Douglas	3083
lime, shale Iatan	3098
lime Lansing	3366
cherty Conglomerate	3410
dolomite Arbuckle	3420 RTD
Total Depth	

TOPS:	
Anhydrite	632
Heebner	2982
Toronto	2995
Douglas	3003
Iatan	3083
Lansing	3098
Conglomerate	3366
Arbuckle	3410

DST #1 3099-3132', op 1 hr, weak steady blow, rec. 30' visible gas, 90' slightly oil & gas cut mud, ISIP 645#/20 min., FP 30#/60#. FSIP 245#/20 min.

DST #2 3261-3272', op 1 hr., rec. 90' visable gas, 30' of slightly oil & gas cut mud, ISIP 182#/20 min. FP 10-10#, FSIP 60#/20 min.

DST #3 3411-3420', op 1 hr, rec. 70' watery mud, ISIP 1125#, FP 30#-60#, FSIP 1035#.