

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

28-19-12W


Company- SINCLAIR OIL & GAS CO.  
Farm- D. C. Johnson "AB" no. 17

SEC. 28 T. 19 R. 12W  
SE NW SW  
990' fr N & W lines of SW/4

Total Depth. 3378  
Comm. 8-17-54 Comp. 8-27-54  
Shot or Treated. 500 gal s. load water 3368-78  
Contractor. G-M-R Drilling Co.  
Issued. 1-1-55

County Barton

KANSAS



Elevation. 1820 KB

Production. Pot. 90 BOPD

CASING:

10 3/4 @ 163' w/ 175 sx cmt.  
7 in. @ 3368' w/ 250 sx cmt/  
2 7/8 3370'

Figures Indicate Bottom of Formations.

sand & gravel	157
sand	163
sand & shale	282
red bed	291
shale	629
anhydrite	646
shale & shells	1517
lime & shale	1574
Ft. Riley lime	1861
shale & lime	2881
lime	3378
Total Depth	

TOPS:

Heebner	2982
Brown lime	3100
Lansing KC	3115
Conglomerate	3362
Arbuckle	3367

GL Measurements

DST #1: 3284-3303, open 1 hr. rec.  
30' mud, SI press. 73