

33-19-12W


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company-W. L. HARTMAN
Farm- Wirtz No. 5

SEC. 33 T. 19 R. 12W
NE SW NE

Total Depth. 3397
Comm. 6-24-52 Comp. 7-10-52
Shot or Treated.
Contractor. H & H Drilling Co.
Issued. 9-27-52

County Barton
KANSAS



CASING:

8 5/8" 129' cem w/110 sx
5 1/2" 3394' cem w/125 sx

Elevation. 1811 D.F.

Production. 114 bbls + 1% wtr

Figures Indicate Bottom of Formations.

clay	10
sand	129
iron	153
shale blue	285
red bed	611
anhydrite	630
shale	1510
lime, shale	2673
lime	2995
lime, shale	3093
lime	3358
conglomerate	3389
congl. & lime	3394
lime	3395
Total Depth Rotary	
lime	3397

Total Depth

Tops:	
Topeka	2709
Heebner	2973
Brown Lime	3093
Lansing	3109
Conglomerate	3358
Arbuckle	3394