

Sw. F.B. Zurich & part

State Kansas County Barton
 Company Messman Lumber Co Well No. 1
 Farm Wells


Survey

Block No. Sec. 31 Twp. 19^U Range 12^W

Co-Ord. 50' no. 7 Elev. 1823 D/F

Cts. NE 1/4 Sec 31

MR Reynolds



34% - G.A. Seeliger Jr
 16% - Ramona F. Seeliger
 6.25% - Humped Collins
 25% - L.J. Plym
 18.75% - Messman Lumber Co.
 Average Depth - W.L. Hall
mu 24568
 3450' test to be com
 by 8-1-66

NOTE: Show Sketch of Lease and Well Location in Above Space

610

Ft. from N. Line

Ft. from S. Line

1980

Ft. from W. Line

Ft. from E. Line

Date	Depth	
7-22-66		Location fixed
8-6		Spud - 8 ⁵ / ₈ " @ 235'
		w/ 200 x 4. am., 4 gal. 4 c.c.
		T.D. @ 6:00 pm 8/6/66
8-8	1195	Relg.
8-9	1825	Relg. Good high in 7th day
8-10	2160	Relg.
8-11	2660	Relg.
8-12	3000	Relg.

Date	Depth	
	3017	Heubner (-1192)
	3134	Bv. Lm. (-1309)
	3149	Lansing (-1324)
O.S.J. #1	3137-82	Op. 35' wk.
		bl. for 19", Rec. 5' mud
		BHP -66-66 [#] Fl. 55-55 [#]
O.S.J. #2	(straddle) - 2480-2537	
		Op. 2 hrs, good blow T.O.
		Rec. 200' mdy wtr
		BHP (30") 933 - (45") 877 [#]
		Fl. - 78-156 [#] , Temp. 92°
8-13	3182	R.J.D.
		with O.S.J. - 8-15-66