


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- WESTGATE-GREENLAND OIL CO.
Farm- Neoland No. 1

SEC. 8 T. 19 R. 12W
SE NE SW

Total Depth. 3455 RB
Comm. 10-13-51 Comp. 10-24-51
Shot or Treated.
Contractor. Jackson Drlg. Corp.
Issued. 12-1-51

County Barton
KANSAS



CASING:
8 5/8" 266' cem. w/160 sx

Elevation. 1857 DF

Production. Dry

Figures Indicate Bottom of Formations.

soil, clay & gravel	45
shale w/sand strks	143
iron pyrite & sand	152
shale & shells	195
pyrite sand	227
shale & sand	260
pyritic sand	264
shale w/strks pyrite	380
red bed	707
anhydrite	733
shale & shells	1225
shale & shells w/salt	1527
lime & shale	2880
lime	3097
shale & lime	3141
brown lime	3159
lansing lime	3385
lime & shale	3405
arbuckle	3455
Total Depth RB	

Tops:	
Anhydrite	707
Heebner	3030
Brown Lime	3142
Lansing	3157
Arbuckle	3403

DST: 3161-93, 5' mud in
10 mins. No. BHP.
3190-3228, open 1 hr. rec.
840' gas, 80' gas cuty mud,
no BHP.
3406-14, open 30 min. rec. 6'
mud, no BHP.
3416-29, open 20 min. rec. 30'
mud, 1100# BHP.

3403
1857
1546