


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
508 E. Murdock  
Wichita, Kansas

Company - ALADDIN PETROLEUM CORPORATION  
Farm - Ahrens No. 1

SEC. 11 T. 19 R. 12W  
NE NE SW

Total Depth. 3403  
Comm. 3-18-50 Comp. 4-3-50  
Shot or Treated.  
Contractor. Crowe Drilling Co., Inc.  
Issued. 5-6-50

County. Barton  
KANSAS



CASING:  
8 5/8" sur. csg. set at 238' R.M. w/  
160 sx con.  
5 1/2" OD csg. set at 3396 1/2 G.M. w/  
150 sx con. Figures indicate Bottom of Formations.

Elevation. \_\_\_\_\_

Production. 891 B/D after 3000  
gals. acid. Test 4-6-50

cly, top soil, shalo	160
iron, shalo	280
shalo, sholls	630
hydrite	670
shalo, sholls	710
shalo, sholls, salt	1385
shalo, sholls	1765
limo sholls, shalo	1900
shalo, limo	1985
shalo, sholls	2220
shalo, limo	2350
shalo, sholls	2445
limo, shalo	2580
shalo, limo	2815
limo	3050
shalo, limo	3100
limo	3380
chert	3400
limo	3403
Total depth	3403

Tops:	
Kansas City	3106 G.M.
Arbucklo	3395 G.M.
Total depth	3397 G.M.

Perf. 3100' to 3178'