


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
508 E. Murdock Wichita, Kansas

Company - ALADDIN PETROLEUM CORPORATION  
Farm - Ahrens No. 3

SEC. 11 T. 19 R. 12W  
NE SE SW

Total Depth: 7 3384, 3378 GM  
Comm. 6-2-50 Comp. 6-21-50  
Shot or Treated.  
Contractor. Crowe Drilling Co., Inc.  
Issued. 8-5-50

County. Barton  
KANSAS



CASING:

8 5/8" 244' cem. w/160 sx  
5 1/2" OD 3376 1/2 GM

Elevation. 1835 D.F.

Production. 526 bbls. oil

Figures Indicate Bottom of Formations.

|                    |      |
|--------------------|------|
| clay               | 150  |
| iron, sand & shale | 245  |
| shale & shells     | 400  |
| redbed             | 485  |
| redbed & shale     | 660  |
| Anhydrite          | 685  |
| shale & shells     | 1650 |
| lime & shale       | 2000 |
| lime               | 2050 |
| shale & shells     | 2625 |
| lime, shale        | 2700 |
| lime               | 3000 |
| lime, shale        | 3085 |
| lime               | 3384 |
| Total depth        |      |
| Ground Measurement | 3378 |

Tops:

|             |         |
|-------------|---------|
| Kansas City | 3123 GM |
| Arbuckle    | 3374 GM |

Remarks:

Perforated 3123-88  
526 bbls./day test 7-13-50  
after 3000 gals. acid.