

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY


508E. Shurdock, Wichita, Kansas

Company - ALADDIN PETRO. CORP.  
Farm - Kultgen "B" No. 1

SEC. 11 T. 19 R. 12W  
NE NE SE

Total Depth. 3434 P.B. 3291½ G.M.  
Comm. 1-24-50 Comp. 3-25-50  
Shot or Treated.  
Contractor. Crowe Drlg. Co.  
Issued. 5-6-50

County. Barton  
KANSAS



CASING:

8 5/8" surface 235' R.M. cem. w/200 sx.  
5 1/2" O.D. 3387' G.M. cem. w/150 sx.

Elevation. \_\_\_\_\_

Production. 81 B/d after acid.

Figures indicate Bottom of Formations.

top soil & clay	165
iron	220
shale	232
pyrites iron	365
shale, shells & redbed	635
anhyd.	660
shale & shells	880
shale, shells, salt	1420
shale, gyp.	1540
lime & shale	2120
shale & shells	2475
lime & shale	2890
lime	2940
lime & shale	3110
lime	3358
lime	3434
Total Depth P.B. 3291½ G.M.	

Geol. tops:

Kansas City	3108 G.M.
Arb.	3397 G.M.

Sout tops:

Heebner	2979
Brn. lime	3097
Lansing	3114
congl.	3374
Arb.	3398

D.S.T. 3117-88

open ½ hr. rec. 60' mud 5000 az.