

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
 508 E. "urdock, Wichita, Kansas

Company LIN OIL CO.
 Farm Panning


No. 1

SEC. 11 T. 19 R. 12W
 SE SE NE

Total Depth. 3408
 Comm. 1-25-50 Comp. 2-3-50
 Shot or Treated. 3500 acid.
 Contractor.
 Issued. 3-25-50

County. Barton

KANSAS



Elevation. _____

Production. Phys. Pot. 89 BOPD
 / 20% wtr.

CASING:

8 5/8"	248'	cem. w/200 sx.
5 1/2"	3401'	cem. w/150 sx.

	Figures Indicate Bottom of Formations.
topsoil, sand	40
sand, shells	205
sand, rock	220
hard sand	223
shale	250
shale, red bed	1295
shale, shells, lime	1585
shale, salt	1895
shale, shells	2245
shale, lime	2680
shale	2785
lime	3408
Total Depth	

Tops:
 Lansing 3110
 Arbuckle 3400

Perforate 3302-08
 " 3189-91
 " 3155-60
 " 3139-45