

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY
 508 EAST MURDOCK - WICHITA, KANSAS

COMPANY ALADDIN PETRO. CORP.

SEC. 12 T. 19 R. 12W
 LOC. SW NW NW

FARM Kultgen "A" NO. 4

TOTAL DEPTH 3414

COMM. 8-9-50

COMP. 8-31-50


BHPT OR TREATED

CONTRACTOR Crowe Drlg. Co. Inc.

ISSUED 4-28-51

COUNTY Barton

KANSAS



CASINO

8 5/8" 238' cem. w/150' sx
 5 1/2" 338 1/4' cem. w/150' sx G.M.

ELEVATION 1794' GM

PRODUCTION 118 BOPD

FIGURES INDICATE BOTTOM OF FORMATIONS

top soil, sand & shells	160
hrd sand & shells	220
sand	240
sand & shale	270
shale & shells	615
anhydrite	635
shale & shells	1545
lime, shells & shale	1690
shale & lime	1785
sandy lime & shale	1855
lime & shale	2025
shale & lime shells	2120
shale & shells	2385
shale, shells & lime	2465
shale & shells	2630
shale & lime shells	2720
lime & shale	2775
lime	3345
conglomerate	3355
lime	3386
arbuckle	3387 1/2
arbuckle	3414
Total Depth	

Scout Tops:

Lansing	3078
Conglomerate	3335
Arbuckle	3390

Set Lane Wells plug @ 3154 G.M.
 Perforated; 3070' to 3144'
 Acidized w/3000 gals.