

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company - LION OIL CO.
Farm - Louis

No. 1

SEC. 12 T. 19 R. 12W
NW NW SW

Total Depth. 3445
Comm. 1-13-50 Comp. 2-13-50
Shot or Treated.
Contractor.
Issued. 3-4-50

County. Barton
KANSAS



Elevation. _____

Production. BHB Pot 1768 BOPD.

CASING:

8 5/8" 265' cem w/200 sx.
5 1/2" 3418' cem w/150 sx.

Figures Indicate Bottom of Formations.

clay, sand	190
shale	220
sand hrd	236
shale	270
shale, redbed	865
shale, shells	1385
lime, shale	1810
lime	2355
lime, shale	2865
lime, sand	2960
lime	3420
dolomite	3445
Total depth	

Tops:
Lansing 3109
Conglomerate 3368
Buckle 3415
Perforated 3152-60'
1000 acid.