


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- Aladdin Petroleum Corp.,
Farm- Hammeke No. 1

SEC. 13 T. 19 R. 12W.
SW SE NW

Total Depth. 3452' R. T. D.
Comm. 4-20-1958 Comp. 5-2-1958
Shot or Treated.
Contractor. Duke Drilling Co.,
Issued. 7-19-1958

County Barton
KANSAS



Elevation. 1816' RB.

Production. 25 BOPD.

CASING:

8 5/8" @ 260'
5 1/2" @ 3442'

Figures Indicate Bottom of Formations.

surface clay	37
River Sand	38
sand-Dry	50
sand & shale	265
shale	320
red bed	630
Anhydrite	650
shale & shells	890
shale	990
shale & shells	1885
lime & shale	2850
lime	2971
Heebner	2980
lime	3355
Conglomerate	3440
Arbuckle	3452

Rotary Total Depth.

TOPS:

Anhydrite	630
Heebner	2971
Lansing	3091
Conglomerate	3355
Arbuckle	3440

Perf. 23/3274-82' Dry.
Perf. 24/3265-73' Dry.
Perf. 12/3253-57'
12/3238-42' Made Abt. 3 Gal of fluid
per. hr. w/few oil specks.

2000 Gal. Acid
Set Plug @ 3190' Perf. 3112-19'
3140-54'. 3000 Gal. Acid. Had bad cement
job, squeezed off perms. W/150 sks.,

Perf. 24/3164-70', 52/3141-54', 20/3127-
32', 16/3113'-17', 24/3103-11'.
Acidized w/6000 gals.
Flowed 80 BBL. Load oil in 1 hr.
And then died, After load oil &
acid recovered on a 10 hr. Swab test,
The well was making 8 BOPH, very
little wtr.,

Well Completed for 25 BOPD.

LANE-WELLS TOPS (Elev. 1811' GL)

Heebner	2966
Toronto	2984
Douglas	3002
Douglas Sand	3016
Brown Lime	3084
Kansas City	3102
Conglomerate	3354
Arbuckle	3435