


WICHITA COUNTY GEOLOGICAL SOCIETY
505 East Maudock,
Wichita, Kansas

Company: SUNRAY OIL CORP.
Farm: H. C. Hermes No. 1

SEC. 18 T. 19 R. 12W
NW NW NE

Total Depth. 3447
Comm. 4-18-52 Comp. 5-1-52
Shot or Treated.
Contractor. Stickle Drlg. Co.
Issued. 8-16-52

County Barton
KANSAS



CASING:

8 5/8" 200'
5 1/2" 3364'

Elevation. 1860 RB

Production. Dry

Figures indicate Bottom of Formations.

surface clay	130
shale & shells	222
iron	260
shale	520
red bed	720
anhydrite	735
shale & shells	1285
shale & lime	1920
lime broken	2027
shale & lime	2295
shale & shells	2455
lime & shale	2535
lime	2645
shale & lime	2775
lime & shale	2975
lime	3447
Total Depth	

Tops:

Heebner	3055
Brown Lime	3162
Lansing	3175
Cherty Congl.	3426

DST: 3192-3219 open 1 hr.
rec. 4' M, 0 BHP
DST: 3230-52' open 1 1/4 hr.
rec. 125' VHOGLM, 50% O,
780' G, 190%
DST 3301-27' open 1 hr. rec.
8' M,)# RTD 3447,
CO 3300, 24/3246-51 sqz. CO
to 3300, 8/3243-45 300-A;
PB 3230; 15/3203-08; 500-A,
CO 3242; 23/3230-38,