

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
Wichita, Kansas

Company - ALADDIN PETROLEUM CORP
Farm - Brodie No. 7

SEC. 23

T. 19 R. 12W
SE NW SE

Total Depth. 3387 G.M.

Comm. 11-24-49

Comp. 12-9-49


Shot or Treated. Acidized -1000 Gal. Acid

Contractor. Hannum Drilling Co

Issued. 2-4-50

County. Barton

KANSAS



Elevation. _____

Production. 204 bbls per day

CASING:

3 5/8 @ 238' w/ 115 sx cement

5 1/2 @ 3376 w/ 150 sx cement

Figures Indicate Bottom of Formations.

clay and sand surface clay	95
shale shells & pyrite	175
pyrite	190
shale shells & sand	240
shale and shells	400
red bed, shale and shell	625
anhydrite	645
shale and shells	815
shale shells and salt	1115
shale and shells	1345
shale and lime	1622
sharp sand	1632
lime and shale	1720
shale and shells	1785
lime	1920
lime and shale	2710
lime	2964
lime and shale	3020
shale and sand	3038
lime and shale	3089
B. lime	3108
lime	3277
lime D. S. T.	3285
lime and shale	3357
cherty conglomerate	3387

Total Depth --G.M.

Tops:

Kans City 3103 G.M.

Arbuckle 3373 G.M.