

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bldg., Wichita, Kansas


Company M. & L. OIL COMPANY
Farm Wagner No. 1

SEC. 23 T. 19 R. 12W
NE NE SW

Total Depth. 3390'6"
Comm. 2-16-48 Comp. 2-29-48
Shot or Treated. Acidized
Contractor H. M. Williams
Issued 5-8-48

County. Barton

KANSAS



Elevation. _____

Production. Dry

CASING:
10-3/4" 177' Cem. W/150 Sx.
5-1/2" 3365' Cem. W/100 Sx.

Figures Indicate Bottom of Formations.

soil, sand, gravel & shale	185
shale blue	290
red bed	625
lime	635
shale & shells	875
shale	910
anhydrite	935
shale & shells	1480
shale & broken lime	1590
lime	1715
lime & shale	2110
lime broken	2161
lime gray	2173
shale & shells	2265
shale & lime	2430
lime hard	2440
lime broken	2540
lime & shale	2640
shale	2685
shale & sandy lime	2718
lime	2925
lime hard	2975
lime	3015
shale	3113
lime	3344
lime & shale	3369
lime Arbuckle RTD	3372'6"
lime & shale	3390'6"
Total Depth	

Tops:
Douglas Sand 3038
Brown lime 3093
Kansas City 3111
Arbuckle Lime 3369

Acidized with 500 gallons acid
at 3380. No increase. 2 bailers
water at 3388' Drilling Completed
on 4-11-48.

Show oil at 3372'6"