

C.L. CARLOCK & ALADDIN PETRO.CO.
Hammer No. 1.

SEC. 35 T.19 R.12W
CNL NE NW

Total Depth. 3370'
Comm. 7-6-40 Comp. 7-21-40
Shot or Treated.
Contractor. Gerbrand-Pulse Oil & Drlg.Co.
Issued. 9-14-40

County. Barton



CASING:
10 " 135'
5 1/2 " 3349'

Elevation.

Production. Pot. 441 B.

Figures Indicate Bottom of Formations.

surface & sand	65
red bed	125
shale & shells	138
sand & iron pyrites	145
sand hrd	151
sand sft	156
iron	157
shale blue & iron	300
red bed	410
shale & shells	1020
shale	1370
shale & shells	1740
lime brkn	1845
shale	1850
lime brkn	1885
chert & iron pyrites	1905
shale & shells	2015
lime	2100
shale	2140
lime	2160
lime brkn	2180
shale	2275
lime	2295
shale & shells	2410
shale	2485
shale & shells	2535
lime	2565
lime brkn	2650
lime	3025
shale sh oil	3108
lime sh oil 3180-83	3346
conglomerate	3349
Arbuckle lime, sh oil	3351
dolomite	3370
Total Depth.	

Carlock & Aladdin #1 Hammer
Sec. 35-19-12W CNL NE NW
Comm. 4-22-42 Comp. 4-29-42
Dry Hole
Perf. 9 shots 3125-29 dry
" 10 " 3172 1/2-77 dry
" 8 " 3177-80 avg
7 gal. fluid per hr w/SSO
Perf. 5 shots 3170-72 no inc.
" 5 " 3129-32 no inc.
" 10 " 3108-18 no inc.
stood 8 hrs, then bailed 12 1/2
gals. wtr w/SSO