

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
503 East Murdock, Wichita, Kansas

Company- RALPH E. HARTMAN  
Farm- Johanning No. 1

SEC. 35 T. 19 R. 12W  
SE SE NE

Total Depth. 3328  
Comm. 11-21-51 Comp. 12-7-51  
Shot or Treated.  
Contractor. Pickrell Drlg.  
Issued. 2-9-52

County Barton  
KANSAS



Elevation. 1800

Production. 138 bbls. / no wtr.

CASING:  
8 5/8" 188' cem. w/150 sx.  
5 1/2" 3326' cem. w/125 sx.

Figures Indicate Bottom of Formations.

cellar	5
sand, clay	20
surface	188
red bed & shale	580
annyd.	595
shale	910
shale & shells	1450
lime	1505
lime & shale	1638
lime brkn	1795
lime	2000
lime & shale	2460
lime brkn	2595
lime & shale	2767
lime	2861
lime hrd	2900
lime	2955
lime & shale brks	3003
lime & shale	3080
lime	3326
Arb.	3328 RTD
Total Depth	

Tops: Scout	
Topeka	2703
Heebner	2940
Brown lime	3058
Mansing	3080
Arbuckle	3326

Meas. from top of rotary bushing