

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - W. L. HARTMAN
Farm - Panning No. 1

SEC. 35 T. 19 R. 12 W
SW NW SW

Total Depth. 3367'
Comm. 12-1-44 Comp. 12-18-44
Shot or Treated.
Contractor. Veeder Supply & Dev'l Co.
issued. 3-17-45

County. Barton
KANSAS



CASING:
8 5/8" 135'
5 1/2" 3351'

Elevation. _____

Production. Pot 165 B.

Figures Indicate Bottom of Formations.

soil - sand	55
sand	115
iron (rough)	128
shale blue	135
shale	210
sand	320
red bed	335
red bed sand	440
red bed, sand, shale	680
red bed, sand	840
anhydrite - shale	985
shale sdy	1150
shale & lime	1380
lime	1810
shale - lime	1935
lime	2240
lime & shale	2335
lime	3075
shale & shells	3120
lime	3352
T. D. Rotary	
lime	3367
Total Depth.	

Tops:	
Brown Lime	3078
White Lansing	3102
Trace Conglomerate	
Arbuckle	3350

3102
1803
1701

- 3181-97 Lime tan wh oolitic good por. & permeability - no oil stain
- 3249-53 Lime tan wh oolitic-poor por. & permeability-poor spotted oil stain-non-commercial show
- 3266-74 Lime wh oolitic-poor por. & permeability-poor spotted dead oil stain-non-commercial show
- 3295-3300 Lime wh slightly oolitic rough-poor por. & permeability-poor spotted oil stain-non-commercial show
- 3350-56 Dolomite tan wh dense-poor spotted stain
- 3356-59 Dolomite tan-fair por.-fair spotted stain
- 3359-63 Dolomite wh dense-no stain
- 3363-67 Dolomite tan-good spotted stain -fair por.