


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bldg., Wichita, Kansas

Company - C. E. ASH ET AL
Farm - F. Wolf "A" No. 2

SEC. 36 T. 19 R. 12W
NE SW SE

Total Depth. 3375'
Comm. 9-5-47 Comp. 11-24-47
Shot or Treated. Acid.
Contractor. C. E. Ash
Issued. 1-24-48

County. Barton
KANSAS



CASING:
8-5/8" 327' Cem. w/160 sx
5-1/2" 3357' Cem. w/ 75 sx

Elevation. _____

Production. Dry

Figures Indicate Bottom of Formations.

sand	70
shale & clay	125
gravel & iron	146
shale & shells	280
shale	295
red rock & shale	555
anhydrite lime	595
red rock & shale	650
sand & shale	985
salt & shale	1370
lime	1775
lime & shale	2695
lime	2935
lime & shale	3010
shale	3080
lime	3085
lime & shale	3355
lime	3360
lime	3375
Total Depth	

Tops: (RB)
Brown Lime 3069
K.C. or White Lime 3089
Conglomerate 3341
Arbuckle Lime 3352

3089
1793
1296

Show free oil 3357-3362
No more oil 3362-3375
Shot marble shot 3360-3370
No increase.

Acid. w/1000 and 3000 gal. No
increase in oil or water.
Ran Gamma Ray Log.

Testing K.C. Lime:
Set plug at 3290'.
Shot 12 shots 3212-16 Showed little
water.
Shot 12 shots 3251-3255 No shows.
Shot 12 shots 3256-3260 No shows.
Acid. w/1000 gal. at 3251-3260-Show
oil and 1 BWPH.
Set plug at 3247'.
Shot 10 shots 3240-3245 Show oil.
Acid. w/1000 and 3000 gal. No inc.
in oil or water.