

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - J..H. HERSHEY ESTATE
Farm - F. Wolf "B" No. 6

SEC. 36 T. 19 R. 12W
CS $\frac{1}{2}$ SE SE

Total Depth. 3368' PB 3354'
Comm. 10-25-47 Comp. 12-6-47
Shor or Treated. Acid.
Contractor. C. E. Ash
Issued. 1-24-48

County. Barton
KANSAS



Elevation. _____

Production. 25 BO

CASING:

8-5/8" 356' Cem. w/175 sx
5-1/2" 3340' Cem. w/ 75 sx

Figures Indicate Bottom of Formations.

sand	50
clay sdy & shale	121
iron shell	132
shale & sand	200
red rock & shale	565
anhydrite	581
red rock & shale	810
shale & shells	1060
salt	1225
shale & shells	1325
lime	1470
shale & lime	2730
lime	2910
shale & lime	3068
lime	3368
Total Depth	
Plugged back to	3354'

Tops: (RB)

Brown Lime	3067
K.C. or White Lime	3086
Conglomerate	3334
ar buckle	3339

3086
1793
1293

Showed 1 $\frac{1}{4}$ BO & no wtr 3339-3354
Shot marble shot 3344-3354
No increase in oil.
acidized w/1000 gal. No increase
in oil.
1 $\frac{1}{4}$ BwPH at 3358-3359
2 BwPH 3364-3368
Plugged back to 3354
Tested 1 $\frac{1}{4}$ BO & no wtr per hr.