

KANSAS DRILLERS LOG


State Geological Survey
WICHITA, BRANCH

API No. 15 — 009 — 20,807
County Number

S. 25 T. 19 R. 13 W
Loc. C W2 SW NW NW

County Barton

640 Acres
N



Locate well correctly

Elev.: Gr. 1831

DF 1834 KB 1836

Operator Nadel & Gussman	
Address 3232 First National Tower Tulsa, Oklahoma	
Well No. #7	Lease Name Wood
Footage Location 1040 feet from (N) line 100 feet from (W) line	
Principal Contractor Woodman & Iannitti Drlg.	Geologist Robert D. Dougherty
Spud Date 5-8-74	Total Depth 3408
	P.B.T.D. 3408
Date Completed 5-16-74	Oil Purchaser

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8-5/8"	28	390	Regular	250	
Production	7-7/8"	5-1/2"	14#	3405	60-40 Pos.	125	12% salt

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
TUBING RECORD			None - Open Hole 3405-08'.		
Size	Setting depth	Packer set at			
2-7/8" OD	3405	None			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
No treatment	

INITIAL PRODUCTION

Date of first production 6-3-74	Producing method (flowing, pumping, gas lift, etc.) Pumping			
RATE OF PRODUCTION PER 24 HOURS	Oil 7 BOPH bbls.	Gas --- MCF	Water Trace bbls.	Gas-oil ratio TSTM CFPB
Disposition of gas (vented, used on lease or sold) Fuel Gas			Producing interval(s) 3405-08 Arbuckle	

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Nadel and Gussman

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

Well No.

7

Lease Name

Wood

Oil

S 25T 19 R 13EX
W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.

TOP

BOTTOM

NAME

DEPTH

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received



Signature

T.P. Harris, Jr.

Chief Engineer

Title

June 18, 1974

Date

K. T. WOODMAN
RES. PHONE 733-0418
OFF. PHONE 265-7650
WICHITA, KANSAS

25-19-13W
D. J. IANNITTI
PHONE 792-2921
GREAT BEND, KANSAS

WOODMAN & IANNITTI DRILLING COMPANY
Rotary Drilling Contractors

15-009-20807

1008 UNION NATIONAL BUILDING
WICHITA, KANSAS 67202

May 17, 1974

Company;	Nadel & Gussmann
Farm;	#7 Wood
Location;	Approximate SW NW NW 1040' from North Line 100' from West Line NW/4
Section;	25-19S-13W
County;	Barton
Contractor;	Woodman & Iannitti Drilling Co.
Comm;	May 8, 1974
Compl;	May 16, 1974
Total Depth	3408'
Casing;	8 5/8" @ 390 w/100 sacks 5 1/2" @ 3405 w/125 sacks

Figures Indicate Bottom Of Formations:

30	Surface Soil
50	Sand
120	Sand & Shale
165	Hard Pack Sand
214	Sand
390	Shale & Sand Streaks
692	Red Bed
700	Anhy
710	Anhy
1450	Shale
1520	Shale & Lime
1690	Shale & Lime
2330	Lime & Shale
2620	Lime & Shale
2900	Shale & Lime
2985	Lime
3180	Lime & Shale
3310	Lime
3380	Lime
3408	Lime



RECEIVED
STATE CORPORATION COMMISSION

MAY 24 1974

CONSERVATION DIVISION
Wichita, Kansas

Woodman & Iannitti Drilling Co.

K. T. Woodman

K. T. Woodman

State Geological Survey
WICHITA, BRANCH