

State Geological Survey

WICHITA, BRANCH

KANSAS DRILLERS LOG

API No. 15 — 009 — 20,970
County Number

Operator
(Sherburne MacLead) ICER ADDIS, Drawer 8038, Wichita, Ks.

Address 841 North Broadway -Wichita, -Kansas-67214- 67208

Well No. #1 Lease Name Green

Footage Location
feet from (N) (S) line feet from (E) (W) line

Principal Contractor H-30, Inc. Geologist Richard M. Foley

Spud Date November 19, 1975 Total Depth 3,380' P.B.T.D.


Date Completed November 28, 1975 Oil Purchaser CLEAR CREEK, INC.

S. 3 T. 19 R. 13 E W

Loc. NE NE NW

County Barton

640 Acres
N



Locate well correctly

Elev.: Gr. 1857

DF KB 1862

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	28#	227'	Common	150	3% Gel, 2% CaCl
Production		8-1/2"	10 1/2#	3,375 1/2'	60-40 Pozmix	100	Salt Sat.

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at			
2-3/8"	3,377				

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production January 16, 1976	Producing method (flowing, pumping, gas lift, etc.) Pumping
RATE OF PRODUCTION PER 24 HOURS Oil 40 bbls.	Gas MCF
Water None bbls.	Gas-oil ratio CFPB
Disposition of gas (vented, used on lease or sold)	Producing interval (s) Arbuckle (Open Hole)

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator ICER ADDIS		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:	
Well No. 1	Lease Name GREEN	OIL WELL	
s3 T 19 R 13 W			
WELL LOG		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.			
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME
Anhydrite	N. A.		
Topeka	2,743		
Heebner	3,032		
Toronto	3,042		
Douglas	3,056		
Brown Lime	3,122		
Lansing	3,135		
Base Kansas City	3,347		
Arbuckle	3,371		
Rotary Total Depth	3,380		
DST #1: Open 30" (30-30-30-30)	3,137	3,170	
Very weak blow; recovered 30' slight oil cut mud; free oil in tool. ISIP 117#, FSIP 64#, IFP 10-10#, FFP 21-21#			
DST #2: Open 60" (30-30-30-30) Weak blow.	3,174	3,215	
Recovered 15' mud, no show. ISIP 573#, FSIP 510#, IFP 21-21#, FFP 32-32#			
DST #3: Open 90" (30-30-60-45)	3,249	3,272	
Fair blow. Recovered 130' gas, 45' slight oil cut water. ISIP 53#, FSIP 43#, IFP 6-6#, FFP 10-10#.			
DST #4: Open 90" (30-30-60-45)	3,372	3,380	
Strong blow. Recovered 140' gas, 500' clean gassy oil, 80' very muddy oil. ISIP 1033#, FSIP 939#, IFP 11-53#, FFP 74-202#			
COMPLETED IN ARBUCKLE, OPEN HOLE			
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.			
RECEIVED STANDARD JAN 29 1976 KANSAS OIL & GAS DIVISION	 Icer Addis Operator Title January 29, 1976 Date		

529E01

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

3-19-13W

COMPANY Mr. Icer Addis

FARM Green

NO. 1

SEC. 3 T. 19S. 13W
LOC. NE NE NW

TOTAL DEPTH 3,380'

COMM. November 19, 1975

COMP. November 28, 1975


SHOT OR TREATED

CONTRACTOR H-30, INC.

ISSUED

COUNTY Barton

KANSAS



CASING

20
15
12
13

10

8 5/8" 227' cemented w/150 sxs cement ELEVATION 1,862' KB

6

5 1/2" 3,375 1/2' cemented w/100 sxs cement

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Shale
Shale and Shells
Lime and Shale
Shale
Shale and Salt
Shale and Lime
Lime and Shale
Shale and Lime
Lime and Shale
Lime
Shale and Lime
Lime
Lime and Shale
Lime
Rotary Total Depth

400'
640'
797'
1,090'
1,600'
1,687'
2,159'
2,740'
3,170'
3,215'
3,269'
3,295'
3,358'
3,380'
3,380'

K. G. S. LIBRARY

I hereby certify the above and foregoing to be
a true and correct log of the above described well
as shown by the drilling reports.

H-30, INC.

Dean Britting

State of Kansas
County of Sedgwick

ss:

Subscribed and Sworn to before me a Notary Public
in and for said county and state this 3rd day of Dec-
ember, 1975.

My Commission Expires:
June 30, 1978

SMPT TOPS DEPTH
TOP 2743
HEEB 3032
TOR 3042
DOUG 3056
BR LM 3122
LANS 3135
BKC 3347
ARB 3371
RTD 3380

Elsie Willison - Notary Public

157625