


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
500 East Murdock, Wichita, Kansas

Company- SOHIO PETROLEUM COMPANY
Farm- Elmer Cook No. 1

SEC. 8 T. 19 R. 13W
SW SW NE

Total Depth. 3469
Comm. 9-11-52 Comp. 9-27-52
Shot or Treated.
Contractor. Harms & Knight Drlg. Co.
Issued. 1-3-53

County Barton KANSAS



CASING:
8 5/8" 427' cem. w/250 sx circ.
5 1/2" 3446'

Elevation. 1858

Production. 190 BO & tr. wtr.

Figures indicate Bottom of Formations.

sand	126
shale & shells	337
sand	364
sand & shale	410
red bed & shale	427
shale & shells	853
anhydrite	878
shale	1157
shale & shells	1296
shale, shells & salt	1420
shale & shells	1615
lime	2035
shale & lime	2320
shale & shells	2650
lime	3099
shale & lime	3217
lime	3430
conglomerate	3449
conglomerate	3469
Total Depth	

Scout Tops:	
Anhydrite	852
Heebner	3095
Dodge	3110
Brown Lime	3188
Lansing	3201
Arbuckle	3443