


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- SIMON LEBOW  
Farm- Prosser No. 1

SEC. 12 T. 19 R. 13W  
NE NE SW

Total Depth. 3487  
Comm. 5-7-52 Comp. 5-18-52  
Shot or Treated.  
Contractor. Quaker Drlg Co., Inc.  
Issued. 11-7-53

County Barton  
KANSAS



CASING:  
8 5/8" 240' cem w/150 sx

Elevation. 1887 R.R.

Production. Dry

Figures Indicate Bottom of Formations.

clay surface, shale	160
sand, shale	240
sand	275
sand, shale	390
red bed, shale	772
anhydrite	800
shale, shells w/streaks of sand & pyrites	1260
lime, shale	2220
lime, shale, shells	2530
lime, shale	3288
lime	3315
lime, shale	3481 RTD
lime	3487
Total Depth	

Tops:	
Heebner	3098
Brown Lime	3202
Lansing	3218
Conglomerate	3460
Arbuckle	3470

Zones of Porosity in the  
Lansing - Kansas City.

Lgt finely xyln w/very lgt spotted stn. Poor porosity, no odor	3224-26
Wht finely xyln dns limestone. Poor poro. no stains, no odor	3255-57
Buff dns finely xyln limestone, poor pin- point poro., no stains, no odor.	3260-63
Buff fossiliferous lime- stone poor to fair poro., no stains, no odor.	3276-3280
White fossiliferous limestone fair to good poro., very lgt spotted stn, no odor	3283-86