

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- MAGNOLIA PETROLEUM CO.
Farm-Dodge Estate No. 1

SEC. 14 T. 19 R.13W
SE SE SE

Total Depth. 3456
Comm. 6-11-53 Comp. 6-21-53
Shot or Treated.
Contractor. Prime Drilling Co.
Issued. 8-15-53

County Barton

KANSAS



CASING:
8 5/8 @ 192' w/ 150 sx cem.

Elevation. 1837 DF

Production. Dry

Figures indicate Bottom of Formations.

sand, clay & shale	160
sand & pyrite	470
shale, shells & red bed	507
shale & shells	570
shale, shells & red bed	980
shale & shells	1590
shale & lime	3175
lime	3456
Total Depth	

TOPS:
Heebner 3041
Brown lime 3149
Lansing KC 3161
Simpson dolomite ? 3407
Arbuckle 3423

DST #1: 3240-55, open 1 hr. stdy blo
rec 630' SW, no SO, SI 20 min. BHP 1160#

DST #2: 3407-26, open 1 hr, wk. int.
blo 10 min, rec. 5' drlg mud, no SO
SI 20 min. BHP 30#