

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

Company- DAVIS BROS.
 Farm- Caraway "A" No. 1

SEC. 19 T. 19 R. 13W
 SE NE SE

Total Depth. 3463.62'

Comm. 1-7-59


Comp. 1-16-59

Shot or Treated.

Contractor. Honaker-Davis Drlg.

Issued. 4-25-59

County Barton
 KANSAS



CASING:

8 5/8" 771' cem w/500 sx.

4 1/2" 3463.62' cem w/200 sx.

Elevation. 1862' KB

Production. 81 BOPD

Figures Indicate Bottom of Formations.

sand & gravel	250
blue shale	300
sand "D"	445
red bed	752
Anhydrite	790
blue shale	1275
salt	1320
shale & shells	1630
lime & shale	2240
shale & lime	2545
lime & shale	2770
shale & lime	2875
lime & shale	3045
shale & lime	3175
lime & shale	3455
chert & shale	3463.62 RTD
Total Depth	

TOPS:	DRILLERS MEAS.	LOG MEAS.
Heebner	3064	3068
Toronto	3078	3081
Douglas	3094	3099
Brown Lansing	3162	3166
White Lansing	3173	3177
Base Kansas City	3393	3397
Conglomerate	3409	3405
Reworked Arbuckle	3454	3458
Solid Arbuckle	3461 ?	Not reached (3465' corrected)

DST #1 3164-3234', op 1 hr, strong blow, rec.
 120' gas, 10' SOGCM, 300' gas cut watery mud
 and muddy water. 20" ICIP 1220#. 30" FCIP
 1160#, FP 60#-170#.

DST #2 3290-3388', op 2 hrs, weak blow thruout,
 rec. 180' gas, 155' VSOCM. 20" ICIP 1040#,
 30" FCIP 640#, (climbing 45°). FP 70#-100#.

DST #3 3376-3462', op 1 hr, fair blow, rec.
 300' gas, 50' HOGCM, 100' MCO, 20" ICIP 1160#,
 30" FCIP 1110#, FP 90#-120#.