

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- HONAKER-DAVIS DRIG. CO.
Farm- Wallace No. 1

SEC. 19 T. 19 R. 13W
SE SW NW

Total Depth. 3481'

Comm. 2-17-56

Comp. 2-29-56


Shot or Treated.

Contractor. Honaker Drlg.

Issued. 5-19-56

County Barton

KANSAS



Elevation. 1867' RB.

Production. 344 BOPD

CASING:

8 5/8" 772' cem w/400 sx
5 1/2" 3480' cem w/125 sx

Figures indicate Bottom of Formations.

surface soil & clay	25
sand	150
shale & shells	290
sand strks & shale	390
shale & shells	465
shale & red bed	765
anhydrite	790
red bed & shale	950
shale & shells	1225
salt	1325
lime & shale	1650
lime	1885
lime & shale	2225
shale & shells	2390
shale & lime	2800
lime & shale	2950
lime	2995
lime & shale	3067
shale	3070
lime & shale	3105
shale	3162
brown lime	3174
lime	3188
shale & sandy lime	3240
lime	3295
lime & shale	3335
lime	3408
Conglomerate	3436
Arbuckle	3481 RTD
Total Depth	

Tops:

Heebner	3067
Brown Lime	3162
Lansing	3172
Conglomerate	3404
Arbuckle	3434

DST #1 3226-3250', tool open 35 mins., closed 25 mins., blow: Gas in 4 mins. rec. flowed oil in 35 mins. BHP 1030#, IFP 340#, FFP 590#.

DST #2 3301-3335', tool open 75 mins., closed in 20 min. Blow: Gas in 8 mins. Rec. 1900' oil BHP 1050#, IFP 130#, FFP 480#.

DST #3 3436-3441', tool open 30", closed 20 mins. weak blow 4 mins., Rec. 10' mud. BHP 0#.

DST #4 3441-3446', tool open 60 mins., closed 20 mins. Rec. 60' oil BHP 0#.

Ran Halliburton Gamma Ray Neutron Log.
Perforated 3462 to 66 with 12 shots. Good show of oil on gun. Acidized with 250 gallon 15% acid by Chemical Process Co.